



APPROXIMATE TOTAL SQUARE FOOTAGE OF ROOF AREA:
20,650 SQ FT CONSISTING OF MAIN ROOF AND SHED ROOF

MAIN ROOF: 17,772 SQ FT CONSISTING OF:

- ±14,834 SQ FT SLOPED ROOF
- ±2,938 SQ FT FLAT MEMBRANE ROOF (SQ FOOTAGE OF MEMBRANE DOES NOT TAKE INTO ACCOUNT REQUIRED OVERLAP OR 24" HIGH PARAPET)

SOUTH SHED ROOF CONSISTING OF:

- ±2,882 SQ FT SLOPED ROOF

REMOVE AND REPLACE EXISTING SLOPED ROOF METAL AND FLAT ROOF MEMBRANE

REPAIR AND REPLACE DAMAGED AREAS OF 1"X ROOF SHEATHING AS NECESSARY WITH 5/8" OR 3/4" CDX/OSB TO MAINTAIN EVEN ROOF PLANE UNDER MEMBRANE ROOFING.

AS WORK PROGRESSES REPORT ANY QUESTIONABLE CONDITIONS TO ENGINEER OF RECORD